Master Plan: 1-Acre Autonomous Agri-Tech Farm

Master Spatial Allocation (The 1-Acre Footprint)

Facility Zone	Allocated Footprint	Primary Function
Aquaponics & Vertical Farm	~30,000 sq. ft.	Core revenue driver; continuous crop and fish cycles.
Logistics & Buffer Zones	~6,760 sq. ft.	20% buffer for internal roads and truck turning radiuses.
Dairy & Biogas Complex	~3,000 sq. ft.	Waste-to-energy and organic fertilizer generation.
Utility & Energy Hub	~3,000 sq. ft.	Water storage, solar inverters, and thermal battery.
Underground Bunker Zone	~800 sq. ft.	Climate-controlled premium crop cultivation.



Component Breakdown & Optimizations

1. The Saffron & Mushroom Bunkers & Light Utility Station (~800 sq. ft.)

- **Description:** Two 40-foot shipping containers placed inside a dug pit with concrete retaining walls.
- **Purpose:** Houses independent, highly controlled aeroponic and hydroponic cycles for premium saffron and exotic mushrooms.
- **Surface Utilization:** The surface level features a lightweight gravel staging area and a post-harvest drying station for immediate processing. It strictly avoids live animal or heavy truck loads to maintain structural integrity.
- **Interconnection:** An elevated standalone solar canopy is anchored directly into the concrete retaining walls. This dedicated canopy generates power for the bunker chillers below.

2. The Aquaponics Greenhouse & Vertical Farm (~30,000 sq. ft.)

- **Description:** A massive surface-level polyhouse dedicated to Deep Water Culture (DWC) or Nutrient Film Technique (NFT) hydroponics.
- **Purpose:** Scales up the fish harvesting ecosystem and filters water through high-yield

exotic crop cultivation.

- **Optimization (Thermal Mass):** Excavated soil from the ~800 sq. ft. bunker pit is used to create earth berms around the exterior base walls. This provides natural insulation, reducing temperature fluctuations and operational power costs.
- **Optimization (Airspace):** Lightweight trellises are strung directly over the Recirculating Aquaculture System (RAS) fish tanks to grow climbing crops in the naturally humid air, creating a new harvestable canopy layer.

3. Integrated Dairy & Biogas Complex (~3,000 sq. ft.)

- **Description:** An on-grade facility housing 3 to 5 dairy cows alongside a biogas digester and slurry tank.
- **Purpose:** Handles all biological waste conversion safely on the surface, generating methane for energy and organic fertilizer. Earth berms from the excavation are also applied here for thermal stability.
- **Optimization (Slurry Processing):** Liquid slurry from the digester is transported to the shaded surface utility station (above the bunkers) to be dried into concentrated fertilizer cakes. This makes the fertilizer lighter to handle and acts as a slow-release nutrient source.

4. Water Management & Energy Hub (~3,000 sq. ft.)

- **Description:** A centralized utility zone housing the borewell head, pump houses, and a large water storage/rainwater harvesting system.
- **Purpose:** Acts as the heart of the farm's power and hydration distribution.
- **Optimization (Thermal Battery):** Your software backend is programmed to over-chill a heavily insulated water reservoir during peak solar hours. At night, this pre-chilled water is circulated to cool the underground bunkers, drastically reducing reliance on expensive chemical batteries.

The Autonomous Interconnections (The System Flow)

This entire micro-ecosystem is bound together by the circular flows your software will manage:

- **The Nutrient & Water Loop:** Fish produce ammonia-rich wastewater. Biofilters convert this into nitrates, which are pumped into the vertical hydroponic systems. The plants filter the water, and clean water recirculates back to the fish tanks. Make-up water is supplied by the main Utility Hub.
- **The Energy & Soil Loop:** Standalone solar panels (mounted on the elevated canopy and facility roofs) power all sensors, pumps, and chillers. Cow waste feeds the biogas plant,

generating supplementary electricity and raw slurry.

- **The Tech Stack:** You will deploy ESP32 or Raspberry Pi hardware across all zones, utilizing pH, Temperature, NPK, CO2, Humidity, Water Level, and Flow Rate sensors. A custom Python/Node.js backend logs this data to a time-series database (like InfluxDB) and visualizes it on a Grafana dashboard, allowing the farm to run autonomously.

Phase 1: Consolidated Equipment, Budget, & Subsidy List

Category	Equipment / Component	Estimated Cost (INR)	Applicable Scheme	Subsidy / Cost Reduction
Underground Bunkers	2x standard 40-foot shipping containers.	₹3,00,000 - ₹4,00,000	N/A (Base infrastructure)	No direct subsidy.
	Excavation and concrete retaining walls.	₹4,00,000 - ₹6,00,000	N/A (Civil works)	No direct subsidy.
	Solar-powered chillers for strict climate control.	₹2,50,000 - ₹4,00,000	NHB (Cold Storage provisions)	Subsidized under infrastructure.
Surface Greenhouse	Surface-level polyhouse covering ~30,000 sq. ft..	₹25,00,000 - ₹35,00,000	NHB & MIDH	Up to 50% reduction.

Category	Equipment / Component	Estimated Cost (INR)	Applicable Scheme	Subsidy / Cost Reduction
Aquaponics & Vertical Farm	RAS (Recirculating Aquaculture System) fish tanks and biofilters.	₹8,00,000 - ₹12,00,000	PMMSY	Up to 40-60% reduction.
	Deep Water Culture (DWC) / Nutrient Film Technique (NFT) hydroponic grow beds.	₹10,00,000 - ₹15,00,000	NHB & MIDH	Up to 50% reduction.
	Lightweight trellises for airspace canopy crops.	₹50,000 - ₹80,000	NHB & MIDH	Up to 50% reduction.
Dairy & Biogas	3 to 5 dairy cows.	₹1,50,000 - ₹3,00,000	National Livestock Mission	Supported / Subsidized.
	Compact biogas digester and slurry tank.	₹1,00,000 - ₹2,00,000	State-level animal husbandry schemes	Supported / Subsidized.
Energy &	Standalone solar panels,	₹10,00,000 -	PM KUSUM (Component	Subsidized for

Category	Equipment / Component	Estimated Cost (INR)	Applicable Scheme	Subsidy / Cost Reduction
Water Hub	inverters, and structural canopy.	₹15,00,000	B)	agriculture.
	Borewell head, water pumps, and a massive 50,000L water storage system.	₹3,00,000 - ₹5,00,000	PM KUSUM (Component B)	Covers standalone solar agriculture pumps.
IoT & Tech Stack	ESP32/Raspberry Pi controllers and local server.	₹50,000 - ₹1,00,000	NHB & MIDH	Covered under high-tech greenhouse integration.
	Sensor Array: NPK, pH/TDS, PT100 temperature, CO2, humidity, water level, and flow rate sensors.	₹1,00,000 - ₹2,00,000	NHB & MIDH	Covered under high-tech greenhouse integration.

Government Scheme Details & Subsidy Coverage

- **National Horticulture Board (NHB) & MIDH:** Offers a capital investment subsidy of up to 50% for setting up high-tech commercial horticulture infrastructure. This covers your surface polyhouses, hydroponic grow beds, trellises, cold storage chillers, and integrated IoT climate control systems.
- **Pradhan Mantri Matsya Sampada Yojana (PMMSY):** Provides substantial financial

assistance (40% for General categories, up to 60% for SC/ST/Women) specifically targeting modern aquaculture technologies like Recirculating Aquaculture Systems (RAS) and biofilters.

- **PM KUSUM Scheme (Component B):** Grants up to a 60% subsidy (30% Central Government, 30% State Government) to farmers for installing standalone, off-grid solar agriculture pumps and solar arrays, provided the land is registered for agriculture.
- **National Livestock Mission (NLM):** State-level and central animal husbandry schemes offer credit-linked subsidies for cattle procurement, dairy farm setup, and integrated biogas and slurry processing units.

Final Phase 1 Budget Summary

Budget Category	Minimum Estimate (INR)	Maximum Estimate (INR)
Base Infrastructure (No Subsidy) *(Shipping containers, excavation, retaining walls)*	₹7,00,000	₹10,00,000
Agri-Tech & Ecosystem (Eligible for Subsidy) *(Greenhouse, Aquaponics, Solar, Dairy, IoT)*	₹63,00,000	₹95,30,000
Total Estimated Cost (Without Schemes)	**₹70,00,000**	**₹1,05,30,000**
Estimated Subsidy Offset (~50% on eligible items)	-₹31,50,000	-₹47,65,000
Final Estimated Cost (After Schemes Availed)	**₹38,50,000**	**₹57,65,000**

Allocated Land Cost (1 Acre): ₹15.0 Lakhs - ₹20.0 Lakhs